


TREE PROTECTION NOTE

- ALL EXISTING TREES WHICH ARE TO REMAIN SHALL BE FULLY PROTECTED WITH HOARDING, ERECTED BEYOND THEIR DRIP LINE PRIOR TO THE ISSUANCE OF THE BUILDING PERMIT. GROUPS OF TREES AND OTHER EXISTING PLANTINGS TO BE PROTECTED, SHALL BE TREATED IN A LIKE MANNER, WITH THE HOARDING AROUND THE ENTIRE CIRCUMFERENCE WITHIN THE PROTECTIVE FENCING SHALL REMAIN UNDISTURBED AND SHALL NOT BE USED FOR THE STORAGE OF THE BUILDING MATERIAL AND EQUIPMENT.
- NO RIGGING CABLES SHALL BE WRAPPED AROUND OR INSTALLED IN TREES AND SURPLUS SOIL, EQUIPMENT, DEBRIS OR MATERIALS SHALL NOT BE PLACED OVER ROOT SYSTEMS OF THE TREES WITHIN THE PROTECTIVE FENCING. NO CONTAMINANTS WILL BE DUMPED OR FLUSHED WHERE FEEDER ROOTS OF TREES EXIST.
- THE DEVELOPER OR HIS/HER/ITS AGENTS SHALL TAKE EVERY PRECAUTION NECESSARY TO PREVENT DAMAGE TO TREES OR SHRUBS TO BE RETAINED.
- WHERE LIMBS OR PORTIONS OF TREES ARE REMOVED TO ACCOMMODATE CONSTRUCTION WORK, THEY WILL BE REMOVED CAREFULLY IN ACCORDANCE WITH ACCEPTED ARBORICULTURAL PRACTICE.
- WHERE ROOT SYSTEMS OF PROTECTED TREES ARE EXPOSED DIRECTLY TO, OR DAMAGED BY CONSTRUCTION WORK, THEY SHALL BE TRIMMED NEATLY AND THE AREA BACKFILLED WITH APPROPRIATE MATERIAL TO PREVENT DESICCATION.
- WHERE NECESSARY, THE TREES WILL BE GIVEN AN OVERALL PRUNING TO RESTORE THE BALANCE BETWEEN ROOTS AND TOP GROWTH OR TO RESTORE THE APPEARANCE OF THE TREES.
- IF GRADES AROUND TREES TO BE PROTECTED ARE LIKELY TO CHANGE, THE OWNER SHALL BE REQUIRED TO TAKE SUCH PRECAUTIONS AS DRY WELLING, RETAINING WALLS AND ROOT FEEDING TO THE SATISFACTION OF THE PLANNING AND BUILDING DEPARTMENT OF THE TOWN OF OAKVILLE.
- GRADE CHANGES WILL NOT OCCUR WITHIN THE TREE PROTECTION ZONE (TPZ) AND/OR NO OPEN TRENCH METHOD OF CONSTRUCTION BELOW-GROUND AS WELL AS NO ABOVE-GROUND LINES WITHIN THE TPZ.



NOTE: TREE PROTECTION ZONES FOR THE PURPOSES OF THIS BY-LAW, THE TREE PROTECTION ZONE (TPZ) FOR ANY TREE SHALL BE DETERMINED AS FOLLOWS:

TRUNK DIAMETER (DBH)*	MINIMUM PROTECTION DISTANCES REQUIRED†
<10 CM	1.8 M
11-30 CM	2.4 M
31-50 CM	3.0 M
51-60 CM	3.6 M
61-70 CM	4.2 M
71-80 CM	4.8 M
81-90 CM	4.8 M

OPEN TRENCHING WILL NOT BE PERMITTED WITHIN TREE PRESERVATION AREA

PROPOSED CONNECTIONS TO BE HORIZONTALLY BORED ONLY NO OPEN TRENCHING

- DIAMETER AT BREAST HEIGHT (DBH) MEASUREMENT OF TREE TRUNK TAKEN 1.4 METERS ABOVE GROUND
- TREE PROTECTION ZONE DISTANCES ARE TO BE MEASURED FROM THE OUTSIDE EDGE OF THE TREE BASE TOWARDS THE DRIP LINE AND MAY BE LIMITED BY AN EXISTING PAVED SURFACE, PROVIDED THAT SURFACE REMAINS INTACT THROUGHOUT SITE ALTERATION




REGIONAL APPROVAL
 REGION DESIGN OF WATER &/OR WASTEWATER SERVICES APPROVED SUBJECT TO DETAIL CONSTRUCTION CONFORMING TO HALTON REGION STANDARDS & SPECIFICATIONS & LOCATION APPROVAL FROM AREA MUNICIPALITY.


SIGNED: INFRASTRUCTURE PLANNING & POLICY

The Applicant should be aware that the approval of the water system on private property is the responsibility of the Local Municipality. Regardless, the Applicant must ensure that the Region of Halton's standards and specifications are met. The Water and Wastewater Layout Design Manual may be obtained from the Data Management Group at 905-825-6032. Furthermore, all water quality tests must be completed to the Region of Halton's satisfaction, before the water supply can be turned on.

SUBJECT TO AN EASEMENT IN FAVOUR OF THE BELL TELEPHONE COMPANY OF CANADA AS IN INST. NO. 565/0



ONTARIO PROVINCIAL STANDARD DRAWING Nov 2015 Rev 2
 LIGHT-DUTY SILT FENCE BARRIER
 OPSD 219.110



KEY PLAN (NOT TO SCALE)


SITE, SERVICING & GRADING PLAN
LOT 6 REGISTERED PLAN 718 TOWN OF OAKVILLE
 REGIONAL MUNICIPALITY OF HALTON

SCALE 1 : 150
J.H. Gelbloom Surveying Limited
 Ontario Land Surveyor
 2022

METRIC Distances shown on this plan are in metres and can be converted to feet dividing by 0.3048.

ITEM DESCRIPTION	PERMITTED (METRES)	ACTUAL (OR PROPOSED) (METRES)
OAKVILLE BY-LAW	2014-014	
ZONING DESIGNATION	RL1-0	
LOT AREA (MINIMUM)	1393.50 SQ.M.	1386.22 SQ.M.
LOT FRONTAGE (MINIMUM)	30.50	34.47
LOT COVERAGE - MAXIMUM	346.55 SQ.M.	258.29 SQ.M.
PROPOSED ADDITIONS: SALINA AND CABANA	25.0%	18.63%
LOT COVERAGE - MAXIMUM	402.00 SQ.M.	353.00 SQ.M.
PROPOSED PATIO (MAXIMUM)	29.0%	25.46%
FRONT YARD SETBACK (MINIMUM)	4.30	7.34
SIDE YARD SETBACK (MINIMUM)	4.20 @ 4.20	7.27 @ 10.31
REAR YARD SETBACK (MINIMUM)	3.50	8.61
OVERALL HEIGHT	9.00	8.33
GARAGE PROJECTION	1.50	0.51
GARAGE FLOOR AREA	56 SQ.M.	55.19 SQ.M.

* PROPERTY IS SUBJECT TO COMMITTEE OF ADJUSTMENTS FILE NO. DESP PERMIT No. 22-
 LEGEND



ESTABLISHED GRADE = (87.79+87.71)/2 = 87.75

NOTE
 EAVES DO NOT PROJECT MORE THAN 0.60M INTO PROPOSED SETBACKS.

All NEW water and sanitary main taps are to be performed by Region of Halton forces only

NOTE
 DOWN SPOUT DISCHARGE LOCATIONS ARE TO BE DISCHARGED ONTO SPLASH PADS.

ANY WATER OR SANITARY SERVICE THAT DOES NOT MEET CURRENT REGIONAL STANDARDS MUST BE DISCONNECTED AT THE MAIN, AND A NEW SERVICE CONSTRUCTED AT THE SITE DEVELOPER'S EXPENSE.

NOTE
 Sewer contractor to verify in the field and provide 2.5m (MIN.) separation between the Water and Sanitary Lines.
 Contractor to use existing services.

NOTE
 If the existing sanitary service lateral is used, it must be inspected at the property line by the Regional Inspector, and televised by Regional forces PRIOR to connection

NOTE
 THIS LOT REQUIRES A SUMP PUMP FOR THE FOUNDATION DRAINS AND SHALL DISCHARGE TO THE DITCH. COMPLETE WITH BACKFLOW PREVENTER.

NOTE
 Service sizes, inverts and types are derived from the Region of Halton Engineering Department Dwg. No. O-10318
 The contractor must verify inverts.

LEGEND

CLF	Chain Link Fence	INV.	Invert Elevation
BF	Board Fence	EG	Established Grade
TFW	Top of Foundation Wall	FF	Finished Floor
MH	Maintenance Hole	T.B.R.	To Be Removed
FF	Finished Floor	705	Top of Slope
UP	Utility Pole	DEC.	Deciduous Tree
CON.	Coniferous Tree	CSP	Corrugated Steel Pipe
DEC.	Deciduous Tree	WV	Water Valve
TOP	Top of Curb	BOC	Bottom of Curb
BOC	Bottom of Curb	HP	High Point
ENTR.	Entrance	RMWL	Rain Water Leader
HP	High Point	TRW	Top of Retaining Wall
TRW	Top of Retaining Wall	BTW	Bottom of Retaining Wall
ARB	Arborist's Tree Number	X	Tree to be Removed
---	Silt Fence		

SITE ADDRESS
 161 DIANNE AVENUE
 OAKVILLE, ONTARIO

SCOTT & BRITANY WESTLAKE (OWNER)
 161 DIANNE AVENUE
 OAKVILLE, ONTARIO

No.	Date	Description	By
1	JUNE 30, 2022	SITE & GRADING	G.S.
2	JULY 19, 2022	SITE & GRADING	G.S.
3			
4			

REVISIONS

INFORMATION TAKEN FROM A SURVEY PREPARED BY J. H. GELBLOOM SURVEYING LTD., O.L.S.
 DATED : MARCH 8, 2022

BENCHMARK
 Elevations are Referred to the Town of Oakville Benchmark No. 46, having an Elevation of 83.6143 m.

SURVEYOR'S CERTIFICATE
 I HAVE REVIEWED THE PLANS FOR THE CONSTRUCTION OF AN 2-STORY ADDITION AND A 1-STORY ENCLOSED PORCH ADDITION FOR THE DWELLING LOCATED AT 161 DIANNE AVE. AND HAVE PREPARED THIS PLAN TO INDICATE THE COMPATIBILITY OF THE PROPOSAL WITH ALL ADJACENT PROPERTIES AND EXISTING MUNICIPAL SERVICES. IT IS MY BELIEF THAT ADHERENCE TO THE PROPOSED ELEVATIONS AND GRADIENTS SHOWN WILL PROVIDE ADEQUATE SURFACE DRAINAGE AND PROPER FACILITY OF THE MUNICIPAL SERVICES WITHOUT DETRIMENTAL EFFECT TO THE EXISTING DRAINAGE PATTERNS OR ADJACENT PROPERTIES.

I HEREBY CERTIFY THAT THE DIMENSIONS AND SET-BACKS ARE CORRECTLY SHOWN.

October 14, 2022
 DATE
 Andrew Musil O.L.S.
 2030

J. H. Gelbloom Surveying Limited
 Ontario Land Surveyor
 476 Morden Road, Unit 102, Oakville, Ont, L6K 3W4
 office@jhgsurveying.ca
 Phone:(905) 338-8210 Fax:(905) 338-9446

Project: 22-001
 Checked By: A.M.
 Drawn By: M.K.
 Party Chief: N.A.

(A) TRANSPORTATION AND WORKS DEPARTMENT



- MUNICIPAL BOULEVARD TO BE RESTORED TO THE SATISFACTION OF ENGINEERING CONSTRUCTION STAFF.
- RESTORE THE PUBLIC ROADWAY TO TOWN STANDARDS AND CLEARLY INDICATE ON THE ENGINEERING DRAWINGS ALL RESTORATION, TO THE SATISFACTION OF THE ENGINEERING & CONSTRUCTION DEPARTMENT.
- DRIVEWAYS ON THE MUNICIPAL RIGHT-OF-WAY SHALL BE PAVED BY THE APPLICANT.
- AT THE ENTRANCES TO THE SITE, THE MUNICIPAL CURB AND SIDEWALK WILL BE CONTINUOUS THROUGH THE DRIVEWAY AND A CURB DEPRESSION WILL BE PROVIDED FOR THE ENTRANCE.
- THE TOPS OF ANY CURBS BORDERING THE DRIVEWAYS WITHIN THE MUNICIPAL BOULEVARD WILL BE FLUSH WITH THE MUNICIPAL SIDEWALK AND ROAD CURB.

(B) GENERAL NOTES

- THE EXISTING GRADES SHOWN ON THIS DRAWING ARE TO REMAIN UNCHANGED.
- THERE IS NO EASEMENTS REGISTERED ON TITLE AND AFFECTING THE SUBJECT LANDS.
- THE STOCKPILING OF CONSTRUCTION MATERIAL TO BE DONE AT THE FRONT OF THE PROPOSED DWELLING ON THE EXISTING DRIVEWAY.
- ALL ROOF DOWNSPOUTS FROM EAVESTROUGH TO DISCHARGE ONTO SURFACE AND THE RUNOFF DIRECTED TOWARDS THE REAR WHERE POSSIBLE AND TO THE ROAD.
- ROOF DOWNSPOUT IS LOCATED IN SUCH MANNER AS TO DIRECT DRAINAGE AWAY FROM WALKWAYS, DRIVEWAYS OR PATIO AREAS.
- MAINTAIN EXISTING GRADES IN AREA AROUND TREES TO BE PRESERVED.
- PRIOR TO CONSTRUCTION, CONTRACTOR TO VERIFY IN FIELD THE EXACT SIZE AND INVERTS OF THE EXISTING WATER SERVICE CONNECTION AND SEWER CONNECTIONS AND REPORT IT TO THE ENGINEER.
- ALL SURPLUS/EXCAVATED MATERIAL TO BE REMOVED FROM THE SITE.
- CONTRACTOR TO MATCH EXISTING GRADES ALONG PROPERTY LINES.
- ALL DISTURBED AREAS WITHIN EXISTING ROAD ALLOWANCE TO BE REINSTATED WITH TOPSOIL AND SOD TO THE SATISFACTION OF THE TOWN OF OAKVILLE.
- THE CONTRACTOR IS TO CHECK AND VERIFY ALL DIMENSIONS, IF ANY DISCREPANCIES, THEY MUST BE REPORTED TO THE ENGINEER IMMEDIATELY PRIOR TO CONSTRUCTION.
- THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES DURING CONSTRUCTION. GAS, HYDRO, TELEPHONE OR ANY OTHER UTILITIES THAT MAY EXIST ON THE SITE OR WITHIN THE STREETLINE MUST BE LOCATED BY ITS OWN UTILITIES AND VERIFIED PRIOR TO CONSTRUCTION.
- ALL CONNECTIONS SHALL BE INSTALLED AS PER REGION OF HALTON STANDARDS AND SPECIFICATIONS.
- BUILDER IS TO VERIFY TO THE ENGINEER THAT THE FINAL FOOTING ELEVATION AND TOP OF FOUNDATION WALL ELEVATION ARE IN CONFORMITY WITH THE BUILDING CODE AND THE CERTIFIED GRADING PLAN PRIOR TO PROCEEDING.
- OUTSIDE FINISHED GRADE TO BE A MINIMUM OF 150 mm BELOW BRICK/STONE VENEER ELEVATION.
- PRIOR TO ANY SODDING, THE BUILDER IS TO ENSURE TO THE SOIL CONSULTANT AND/OR THE ENGINEER THAT THE LOT HAS BEEN GRADED AND TOPSOILED AND SODDED COMPLETELY WITH A MINIMUM DEPTH OF 200 mm OF TOPSOIL AND N° 1 NURSERY SOD AND A MINIMUM DEPTH OF 150 mm CRUSHED STONE TO BE PROVIDED ON THE ENTIRE LENGTH OF EACH DRIVEWAY ON A FIRM SUBGRADE AND THE DRIVEWAY TO BE PAVED WITH A MINIMUM COMPACTED DEPTH OF 75 mm OF ASPHALT BETWEEN THE CURB AND THE GARAGE.
- NO SODDING ON ANY LOT IS PERMITTED UNTIL PRELIMINARY INSPECTION IS DONE BY THE ENGINEER AND THE BUILDER.
- DRIVEWAY GRADES SHOULD BE NOT LESS THAN 1.0% AND NOT GREATER THAN 7.0%.
- LAWN AND SWALES SHALL HAVE MINIMUM SLOPE OF 2.0% AND A MAXIMUM SLOPE OF 5.0% AND HAVE A MINIMUM DEPTH OF 150mm.
- WHERE GRADES IN EXCESS OF 5.0% ARE REQUIRED, THE MAXIMUM SLOPE SHALL BE 3:1. GRADE CHANGES IN EXCESS OF 1.0 m ARE TO BE ACCOMPLISHED BY USE OF A RETAINING WALL. RETAINING WALLS HIGHER THAN 0.6 m SHALL HAVE A FENCE INSTALLED ON THE HIGH SIDE.
- THE SERVICE CONNECTION TRENCH THROUGH THE TRAVELLED PORTION OF THE ROAD ALLOWANCE SHALL BE BACKFILLED WITH UNSHRINKABLE BACKFILL MATERIAL AS PER TOWN OF OAKVILLE STANDARDS UNLESS OTHERWISE SPECIFIED PRIOR APPROVAL FOR OTHER BACKFILL MATERIAL HAS BEEN OBTAIN.
- ALL WATERMANS AND WATER SERVICE MATERIALS AND CONSTRUCTION METHODS MUST CORRESPOND TO CURRENT REGION OF HALTON STANDARDS AND SPECIFICATIONS.
- WATERMANS AND/OR WATER SERVICES ARE TO HAVE A MINIMUM DEPTH OF 1.7 m WITH A MINIMUM HORIZONTAL SPACING OF 2.5 m FROM THEMSELVES AND OTHER SERVICES.
- SEDIMENT CONTROL FENCE TO BE INSTALLED AS PER THE TOWN OF OAKVILLE STANDARDS.
- ALL DAMAGED AND DISTURBED AREAS TO BE REINSTATED WITH TOPSOIL AND SOD.

EROSION AND SILTATION NOTES

- ALL EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED ACCORDING TO APPROVED PLANS TO COMMENCEMENT OF ANY EARTH MOVING WORK ON THE SITE AND SHALL REMAIN IN PLACE UNTIL A DISTURBED AREAS ARE STABILIZED WITH THE INTENDED FINAL GROUND COVER.
- EROSION AND SEDIMENT CONTROLS SHALL BE INSPECTED BY THE BUILDER/DEVELOPER.
 - WEEKLY
 - BEFORE AND AFTER ANY PREDICTED RAINFALL EVENT
 - FOLLOWING AN UNPREDICTED RAINFALL EVENT
 - DAILY, DURING EXTENDED DURATION RAINFALL EVENTS
 - AFTER SIGNIFICANT SNOW MELT EVENTS
- EROSION AND SEDIMENT CONTROLS SHALL BE MAINTAINED IN PROPER WORKING ORDER AT ALL TIMES. DAMAGED OR CLOGGED DEVICES SHALL BE REPAIRED WITH 48 HOURS.
- WHERE A SITE REQUIRES DEWATERING AND WHERE THE EXPELLED WATER CAN BE FREELY RELEASED TO A SUITABLE RECEIVER, THE EXPELLED WATER SHALL BE TREATED TO CAPTURE SUSPENDED PARTICLES GREATER THAN 40 MICRON IN SIZE. THE CAPTURED SEDIMENT SHALL BE DISPOSED OF PROPERLY PER MOECC GUIDELINES. THE CLEAN EXPELLED WATER SHALL BE FREELY RELEASED TO A SUITABLE RECEIVER IN MANNER THAT DOES NOT CREATE DOWNSTREAM ISSUES INCLUDING BUT NOT LIMITED TO EROSION, FLOODING- NUISANCE OR OTHERWISE, INTERFERENCE ISSUES, ETC.
- EXISTING STORM SEWERS AND DRAINAGE DITCHES ADJACENT TO THE WORKS SHALL BE PROTECTED AT ALL TIMES FROM THE ENTRY OF SEDIMENT/SILT THAT MAY MIGRATE FROM THE SITE. FOR STORM SEWERS: ALL INLETS(REAR LOT CATCHBASINS, ROAD CATCHBASINS, PIPE INLETS, ETC.) MUST BE SECURED/FITTED WITH SILTATION CONTROL MEASURES. FOR DRAINAGE DITCHES: THE INSTALLATION OF ROCK CHECK DAMS, SILTATION FENCING, SEDIMENT CONTAINMENT DEVICES MUST BE INSTALLED TO TRAP AND CONTAIN SEDIMENT. THESE SILTATION CONTROL DEVICES SHALL BE INSPECTED AND MAINTAINED PER ITEMS 2 AND 3 ABOVE.
- IN THE EVENT OF A SPILL(RELEASE OF DELETERIOUS MATERIAL) OR EMANATING FROM THE SITE, THE OWNER AGENT SHALL IMMEDIATELY NOTIFY THE MOECC AND FOLLOW ANY PRESCRIBED CLEAN UP PROCEDURE. THE OWNER OR OWNERS AGENT WILL ADDITIONALLY IMMEDIATELY NOTIFY THE TOWN.




(C) UTILITIES CONNECTION

- SANITARY: (A) MUNICIPAL SANITARY SEWER AVAILABLE ON THE SITE.
- WATER: (A) SERVICE CONNECTIONS TO BE 25mm DIA. TYPE 'K' SOFT COPPER TUBING UNLESS OTHERWISE NOTED AS PER REGION OF HALTON STANDARDS.
- STORM: (A) A SUMP PUMP WILL BE REQUIRED TO DRAIN THE BASEMENT FACILITIES.

To re-use existing water service providing it meets Current Standards (otherwise, use proposed 25mm Copper Type-K water service)
 The existing water service must be inspected at the property line by the Regional Inspector.

The existing sanitary lateral must be inspected at the property line by the Regional Inspector, and televised by Regional forces PRIOR to connection.
 A lateral that does not meet current regional standards must be disconnected at the main. A Revision to the Service Permit, drawings and payment of applicable fees is required.



EAST ELEVATION

WESTLAKE ADDITION
OAKVILLE, ONTARIO

1/8" = 1'-0"
11.OCT.2022

sbd steven brousseau design
Architecture. Design.



NORTH ELEVATION

1/8" = 1'-0"
11.OCT.2022

WESTLAKE ADDITION
OAKVILLE, ONTARIO

sbd steven brousseau design
Architecture. Design.




WEST ELEVATION

1/8" = 1'-0"
11.OCT.2022

WESTLAKE ADDITION
OAKVILLE, ONTARIO

sbd steven brousseau design
Architecture. Design.



SOUTH ELEVATION


1/8" = 1'-0"
11.OCT.2022

WESTLAKE ADDITION
OAKVILLE, ONTARIO

sbd steven brousseau design
Architecture. Design.

October 14th, 2022

Committee of Adjustment
1225 Trafalgar Road
Oakville, ON
L6H 0H3



Steven Brousseau Design

**Architectural
Design**

— phone
905 541 7661

— info@
stevenbrousseaudesign.com

RE: Application for minor variance @ 161 Dianne Ave, Oakville, ON L6J 4G8

Dear Committee of Adjustment Council Members,

My clients seek your approval to rebuild an existing attached garage with new RFA above in their rear yard.

The reason we seek approval is due to the uniqueness of the site as zoning has revealed the North side of their property as the front of the house. This is counter intuitive to our assumptions as the front door of their house as well as the garage doors are facing West. Due to this issue, the building depth measurement is required to be calculated along the building's length and not it's width. Moreover, what should be our interior side yard is defined as our rear yard.

Therefore, we are asking relief for the following two bylaw requirements:

- Our existing building depth is currently at 23.99m while our new building depth is proposed to be 25.56m (Bylaw is 20.00m).
- Our existing rear yard setback is 10.02m to be reduced to 8.61m (Bylaw is 10.5m).

If you have any questions or comments, feel free to contact me. Thank you for your time.

Sincerely,

Steven Brousseau

Principal | *Steven Brousseau Design*
info@stevenbrousseaudesign.com
(905) 541-7661